

15135.23749.0000

LEASE NAME Bankoff Minerals

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Bankoff Oil Company

SEC. 9 TWP. 20S RGE. 24W (E) or (W)

ADDRESS Box 1374, Great Bend, KS 67530

COUNTY Ness

PHONE# (316) 793-2061 OPERATORS LICENSE NO. 6040

Date Well Completed

Character of Well Oil

Plugging Commenced 11-2-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-5-93

The plugging proposal was approved on (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4428'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	315.92	none.
				5 1/2	4404'	1989'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 4350' & 5 sks cement. Shot @ 2609', worked pipe, swedged on. Shot @ 2311, worked pipe, left on tension. Shot @ 1989. Pulled to 1550, pumped 10 sks gel & 50 sks cement. Pulled to 900, pumped 80 sks cement. Pulled to 350, pumped 50 sks. Pulled tp 40', pumped 10 SK. Pulled rest of pipe, topped off. 60/40 pos, 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS. 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bankoff Oil Company

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 93

My Commission Expires:



RECEIVED
Notary Public

NOV 29 1993
Form CP-4
Revised 05-88
CONSERVATION DIVISION
Wichita, Kansas