


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 8 Twp. 20 Rge. 24 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines. C SE NE
Lease Owner Pickrell Drilling Company
Lease Name Slagel Well No. 2
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 9-24-65 19____
Plugging completed 9-30-65 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gib Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4406' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	274'	None
				5-1/2"	4394'	2410'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pumped plug to 4011', sanded hole to 3300' and dumped 4 sacks of cement with dump bailer. Pulled 5 1/2" casing to 600' and pumped in 10 sacks of gel mud @ 600'. Pulled 5 1/2" casing to 500' and pumped in 20 sacks of cement. Pulled 5 1/2" casing to 275' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, set rock bridge @ 40' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1965


CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS
(If additional description is necessary, use BACK of this sheet)

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)



SUBSCRIBED AND SWORN TO before me this 4th day of October, 1965

Milton J. Volier
Notary Public.

My commission expires May 20, 1968

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 4th National Bank Bldg
Wichita, Kansas.

Rotary Drilling Commenced 8-23-65

Rotary Drilling Completed 9--5-65

LOCATION: Slagle No. 2, C SE NE Section 8-20-24W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (12 jts) 8 5/8" surface casing set at 251', cemented with 160 sacks cement. Circulated. Completed 8:30 P.M. August 23, 1965.
(142 jts) 5 1/2" casing set at 4394' with 75 sacks cement. Completed 1:30 A.M. September 6, 1965.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

120	Clay & Shells	C. F. S.
800	Shale & Shells	4170
974	Red Bed, Shale & Shells	4286
986	Blaine	4300
1055	Red Bed, Shale & Shells	4315
1285	Sand	4376
1611	Shale & Shells	4378
1628	Anhydrite	4390
2195	Shale & Shells	4399
2515	Shale & Lime	4403
2685	Lime	4408
3075	Lime & Shale	
3260	Shale & Lime Stringers	Slope Tests
3370	Lime & Shale	1500
3505	Sandy Shale & Lime	2500
3615	Shale & Lime	3500
3710	Sandy Lime & Shale	4000
3840	Lime & Shale	
3910	Shale, Chalk & Lime	S. L. M.
4020	Lime	2457
4065	Lime & Shale	3128
4125	Lime	3905
4205	Lime & Shale	
4250	Lime	
4276	Pawnee	
4284	Shale	
4286	Ft. Scott	
4355	Lime	
4378	Lime & Chert	
4385	Conglomerate	
4408	Mississippian -RTD	

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1965

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 16th day of September, 1965, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public