

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-159-21,949.0000

LEASE NAME Johnson

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 TWP. 21 RGE. 7 (X) or (W)

COUNTY Rice

Date Well Completed

Plugging Commenced 10-3-97

Plugging Completed 10-6-97

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Milton Lackey

ADDRESS 382 1st Avenue Inman, Ks. 67546-8632

PHONE# 316) 585-2119 OPERATORS LICENSE NO. 9132

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	215'	
				5 1/2"	3468'	2638'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded at 3297'. Bailed 5 sks cement. Shot at 2819' & 2747'. Shot at 2638'. Pulled to 1050'. Pumped 35 sks cement. Pulled to 600'. Pumped 35 sks cement. Pulled to 250'. Circulated 92 sks cement to surface. Pulled the rest of the pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 249 E. Beth Drive Sterling, Ks. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Milton Lackey

STATE OF Kansas COUNTY OF Reno, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Milton Lackey


(Address) 382 1st Ave, Inman, Ks 67546

SUBSCRIBED AND SWORN TO before me this 15 day of Oct., 19 97

Kathy Biggs
Notary Public

My Commission Expires: 12-7-97

USE ONLY ONE SIDE OF EACH FORM



Form CP-1
Revised 05-88