

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 26 TWP. 21S RGE. 12W E/W  
Location as in quarters or footage from lines:  
SW NW NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Austin Widener  
Lease Name Widener #2 Well No. \_\_\_\_\_  
Office Address R.R. #3, Hudson, Ks. 67545  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 5/26/81  
Plugging completed 5/29/81  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3661'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	279	None
				4 1/2"	3658'	1802'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Pushed plug to 3275'. Sanded to 3225 and set 4 sacks cement. Pulled 17" stretch. Made shots at 2783, 2672, 2554, 2437 and 2321. Not loose. Stretch 17" min and 21" max. Shot again at 2204, 2109, 1972, 1894 and 1816. Worked pipe free and pulled total string of 47 joints. Plugged well with 125 sacks cement, 25 sacks gel and 8 sacks hulls. 300# shut in pressure. Plugging complete.

RECEIVED  
STATE CORPORATION COMMISSION


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING JUN - 4 1981

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 81

My Commission expires:  Joan Kelso  
Notary Public.