

15.185.01043.0001

TYPE OR PRINT

NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

Widener

WELL NUMBER #1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 26 TWP. 21SRGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 10-14-91

Plugging Commenced 12-6-93

Plugging Completed 12-8-93

LEASE OPERATOR HELM ENERGY COMPANY

ADDRESS 6104 E. 32nd Street, Suite 207 Tulsa, OK 74135

PHONE#(918)665-3740 OPERATORS LICENSE NO. 03672

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 12, 1993 (date)

by CASE MORRIS (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Viola Depth to Top 3,554' Bottom 3,594' T.D. 3,747'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Viola	Lime/Chert	3,544	3,594	5 1/2"	3,747	1,765'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each so dumped 2 yrd Sand + 5 Sacks Cement with glass bottoms bailer; pulled 1,765' of 5 1/2" casing; Pumped 300 lb Hulls: 10 Sacks Gell: 50 Sacks Cement; 10 Sacks Gel: 100 lb Hulls: Release Top Plug: 125 Sacks Cement; Shut-In; cut Off surface Pipe and Weld Cap.

Name of Plugging Contractor KLIMA WELL SERVICE, INC. License No.

Address P.O. BOX 386, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HELM ENERGY COMPANY

STATE OF Oklahoma COUNTY OF Tulsa, ss.

HELM ENERGY COMPANY

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature)

(Address) 6104 E. 32nd St, Suite 207 Tulsa, OK 74135

SUBSCRIBED AND SWORN TO before me this 11TH day of February, 1994

Shyllie A. STATE NOTARY PUBLIC Notary Public

My Commission Expires:

March 7, 1997

FEB 21 1994

USE ONLY ONE SIDE OF EACH FORM

CONSERVATION DIVISION Wichita, Kansas

Form CP-1 Revised 05-88