

STATE OF KANSAS
STATE CORPORATION COMMISSION

Orig - STATE CORP. Comm. ✓
Copy - OKLA. CITY OFFICE
Copy - VON ROE - 343 FPB
Copy - Well FILE
WELL PLUGGING RECORD


FORM CP-4

15.185.20845.0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 26 Twp. 21S Rge. 12 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

NW NW SE
Lease Owner Phillips Petroleum Company
Lease Name Widener Farms "A" Well No. 1
Office Address 7th Floor, 100 Park Ave, Bldg, Oklahoma City
Character of Well (Completed as Oil, Gas or Dry Hole) 73102



Dry Hole
Date Well completed 9/9/78 19
Application for plugging filed 9/9/78 19
Application for plugging approved 9/9/78 19
Plugging commenced 9/9/78 19
Plugging completed 9/9/78 19
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3700'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug @ 3710' KB - 5 sx common, set plug @ 3500' to 3200', 100 sx common; 540' - 300' 95 sx common; 30' - 2' 12 sx common; 2 sx rathole, 2 sx mousehole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & N Drilling, Division of Benson Mineral Group, Inc.

STATE OF KANSAS COUNTY OF MONTGOMERY, ss. contractor Lucille Shukers (employee of ~~xxxx~~) or (~~xxxx~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lucille Shukers
Box 846, Independence, Kansas 67301
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1978

Jane McNickle
Notary Public.

My commission expires 9/24/78

JANE McNICKLE
NOTARY
PUBLIC
Montgomery County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1978
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

S. 26 T. 21 R. 12 $\frac{1}{2}$ W

API No. 15 — 185 — 20,845
County Number

Loc. NW NW SE

Operator

County Stafford

Phillips Petroleum Company

640 Acres
N

Address P. O. Box 287 Great Bend, Kansas 67530



Well No. #1 Lease Name Widener Farms "A"

Elev.: Gr. 1828'

Footage Location 2310' feet from (S) line - 2310' feet from (E) line

Principal Contractor B & N Drilling Co. Geologist J. C. Musgrove

Spud Date 8-29-78 Total Depth 3710' P.B.T.D.

DF KB 1838'

Date Completed 9-9-78 Oil Purchaser None - Dry Hole

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	24 1/2	345.21'	Class A	350	2% Gel, 3% Cal Chl., & 1/4% Flocele/sk

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1979
CONSERVATION DIVISION
Wichita, Kansas

INITIAL PRODUCTION

Date of first production None Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS Oil Gas Water Gas-oil ratio
bbls. MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Phillips Petroleum Company

15.185.20845.0000

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Widener Farms "A"

Dry Hole

S 26 T 21 R 12 W

Stafford County, Kansas

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface	0'	345'		
Sand and Clay	345'	909'		
Lime and Shale	909'	1659'		
Lime and Shale	1659'	2535'		
Shale and Lime	2535'	3019'		
Lime and Shale	3019'	3350'		
Lime and Shale	3350'	3368'		
Lime and Shale	3368'	3550'		
Shale and Lime	3550'	3710'		
T.D.	3710'			

RECEIVED
 STATE CORPORATE COMMISSION
 JAN 18 1979
 CONSERVATION DIVISION
 Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

C. D. Dohrer

C. D. Dohrer
District Superintendent

Signature

Title

September 12, 1978

Date