

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County. Sec. 26 Twp. 21 Rge. 12 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE NE NW


Lease Owner L. D. Davis  
Lease Name Widener Well No. A-1  
Office Address Box 324, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed 2-24 1979  
Application for plugging filed 2-24 1979  
Application for plugging approved 2-24 1979  
Plugging commenced 2-24 1979  
Plugging completed 2-24 1979  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3690'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	306'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Plugged w/50/50 Pozmix  
50 sks. @ 600'  
40 sks. @ 300'  
12 sks. @ 40'  
3 in the rathole - By Howco - Job completed 2:45 p.m.

RECEIVED  
STATE CORPORATION COMMISSION

MAR - 6 1979


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company  
P. O. Box 1389, Great Bend, KS 67530  
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
Allen Drilling Company (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Dale L. Smith  
P. O. Box 1389, Great Bend, KS 67530  
(Address)



SUBSCRIBED AND SWORN TO before me this 26th day of February, 1979

Glenda Nichols  
Notary Public.

My commission expires 1-28-1980

DRILLER'S WELL LOG

DATE COMMENCED: 2-19-79  
 DATE COMPLETED: 2-24-79

L. D. Davis  
 Widener #A-1  
 SE NE NW, Sec. 26-21-12  
 Stafford County, Kansas

ELEVATIONS 1838 K.B.  
 1833 G.L.

FORMATION DATA

617- 624' Anhydrite  
 3123-3128' Shale  
 3128-3142' Lime  
 3142-3155' Lime  
 3155-3254' Shale  
 3254-3270' Lime and Shale  
 3270-3508' Lime  
 3508-3543' Lime and Shale  
 3543-3628' Shale, Lime, Chert and Sand  
 3628-3654' Chert  
 3654-3690' Simpson Shale  
 3690' T.D.

Anhydrite	617	
Heebner	3123	-1285
Toronto	3142	-1304
Douglas	3155	-1317
Brown Lime	3254	-1416
Lansing KC	3270	-1432
Base KC	3508	-1670
Conglomerate	3543	-1705
Viola	3628	-1790
Simpson Shale	3654	-1816
RTD	3690	-1852

SURFACE PIPE:

Ran 8 Jts. Used 20# 8 5/8".  
 Tallied 298'. Set @ 306' w/250 sks.  
 60-40 Pozmix, 2% Gel, 3% c.c.  
 By Howco, cement did circulate.

PLUGGING:

Plugged w/50-50 Pozmix  
 50 sks. @ 600'  
 40 sks. @ 300'  
 12 sks. @ 40'  
 3 sks. in the rathole  
 By Howco. Job completed 2:45 p.m.

RECEIVED  
 STATE CORPORATION COMMISSION

MAR - 9 1979


CONSERVATION DIVISION  
 AFFIDAVIT  
 W. DAVIS  
 Kansas

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss.

DALE L. SMITH, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

*Dale L. Smith*  
 \_\_\_\_\_

Subscribed and sworn to before me this 26th day of February 1979.



*Wanda Quibb*  
 \_\_\_\_\_  
 (Notary Public)

My commission Expires: 1-28-1980