

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-185-22,778.0000

LEASE NAME Widener

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4290 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 26 TWP. 21 RGE. 12 (E) or (W)

LEASE OPERATOR A.C. Widener Farms, Inc.

ADDRESS RR #3 Hudson, KS 67545

COUNTY Stafford

PHONE#(316) 458-3331 OPERATORS LICENSE NO. 7893

Date Well Completed 06-03-91

Character of Well D & A

Plugging Commenced 06-03-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 06-03-91

The plugging proposal was approved on 05-31-91 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3641

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

RECEIVED
STATE CORPORATION COMMISSION
JUN 06 1991
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 660' w/50 sacks cement thru drill pipe
Next Plug: @ 330' w/50 " " " " " " 15 sacks in Rat Hole
Top Plug: @ 40' w/10 " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. C. Widener Farms, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or (~~Operator~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 91

Paula Ann Ladd
Notary Public

My Commission Expires: _____



15.185.22778.0000

DRILLER'S WELL LOG

DATE COMMENCED: May 29, 1991
DATE COMPLETED: June 3, 1991

A.C. Widener Farms, Inc.
WIDENER #4
SE NW NW
Sec. 26, T21S, R12W
Stafford County, Ks.

0 - 302' Surface Soil, Clay, Shale
302 - 615' Red Bed
615 - 637' Anhydrite
637 - 1399' Shale
1399 - 2842' Shale w/lime streaks
2842 - 3124' Lime
3124 - 3155' Shale & Lime
3155 - 3257' Shale
3257 - 3275' Shale & Lime
3275 - 3508' Lime
3508 - 3546' Shale & Lime
3546 - 3583' Chert
3583 - 3633' Shale & Sand
3633 - 3641' Dolomite
3641' RTD

ELEVATION: 1850 K.B.

Surface Pipe: Set used
8-5/8", 28# pipe @ 302'
w/180 sacks 60/40 pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 5th day of June 1991.



Paula Ann Laudick
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1991

CONSERVATION DIVISION
Wichita, Kansas