

STATE OF KANSAS
STATE CORPORATION COMMISSION

15.185.20843.0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 26 Twp. 21 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
100' West of SE SW NE

Lease Owner L. D. DAVIS
Lease Name WIDENER Well No. 2


Office Address P. O. Box 324 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed August 16 1978
Application for plugging filed August 16 1978
Application for plugging approved August 16 1978
Plugging commenced 7:15 P.M. August 16 1978
Plugging completed 8:15 P.M. August 16 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation Depth to top Bottom Total Depth of Well 3645
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug at 540'---W/40 sx. 50/50 Pozmix, 2% Gal.
Middle Plug at 270'----W/40 sx " " "
Top Plug at 40' with 1/2 sk hulls, 12 sx cement
3 sacks in rat hole

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF Kansas COUNTY OF Barton, ss.
Wayne Dobbs (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1978

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

L. D. DAVIS - OPERATOR

WIDENER # 2
100' West of SE SW NE
SEC. 26-21-12
STAFFORD COUNTY, KANSAS

ELEV. 1830 K.B.
T. D. 3645

COMMENCED: 8-9-78
COMPLETED: 8-16-78

CASING:

8-5/8" set at 291'

CEMENT:

W/250 sx. 60/40 Pozmix, 2% Gel

FORMATION

Sand
Shale
Anhy.
Shale & Shells
Lime & Shale
Shale
Lime & Shale
Re-worked arb.
Arb. Dolomite

DEPTH

0 - 200
200 - 593
593 - 613
613 - 1500
1500 - 3104
3104 - 3108
3108 - 3590
3590 - 3622
3622 - 3645

TOPS

Anhy.
Heebner
Toronto
Douglas
Brown Lime
Lansing
Base K/C

593
3104
3124
3137
3234
3253
3486
3510
3536
3547
3590
3622
3645

Reworked Arb.
Arb.
R.T.D.

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1978

CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

State of KANSAS County of BARTON

I, Wayne Dobbs of the L. D. Drilling Company

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Wayne Dobbs
Wayne Dobbs

Subscribed and sworn to before me on this 17th day of August 1978

My commission expires: 5-20-81

Bessie M. Dewerff
Notary Public: Bessie M. Dewerff

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81