

STATE OF KANSAS  
OIL CORPORATION COMMISSION  
5 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-185-21,546-00-00

LEASE NAME Siefkes

WELL NUMBER #4

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 26 TWP. 21 RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed 4-16-82

Plugging Commenced 5-17-02

Plugging Completed 5-21-02

RECEIVED  
5-31-02  
MAY 31 2002

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, Ks. 67530

PHONE (620) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Oil

Use Oil, Gas, D&A, SWD, Input, Water Supply Well

A plugging proposal was approved on \_\_\_\_\_ (date)  
Richard Lacey (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3700

Give depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	255'	None
				5-1/2"	3697'	1620'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 3300' and 5 sacks cement. Shot pipe @2600', 2200', 2000', 1800' and 1620'. Pulled pipe up to 630', pumped 10 sacks gel, 50 sacks cement and 200# hulls, pulled up to 280', pumped 50 sacks cement, pulled up to 40' and circulated 20 sacks cement to surface. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L.D. Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
do hereby certify that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 30th day of May 2002

Irene Herzberg  
Notary Public

My Commission Expires:

