

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 26 Twp. 21S Rge. 12W (X) (W)

Location as "NE/CNW4SW4" or footage from lines SE SE SW
Lease Owner Petroleum, Inc. and Graves Drilling Co., Inc.
Lease Name Siefkes Well No. 1
Office Address Box 332, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 10, 1962
Application for plugging filed October 10, 1962
Application for plugging approved October 10, 1962
Plugging commenced October 10, 1962
Plugging completed October 10, 1962
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr., Stafford, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3659 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 275 feet with heavy mud. Set plug at 275 feet with 1/4 sack hulls and rock on plug with 20 sacks cement. Filled hole to 40 feet with mud. Set plug at 40 feet with 1/4 sack hulls and 15 sacks cement. Plugged rat hole with 2 sacks cement.

10-17-62

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address Box 332, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
JOHN C. GRAVES (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
Box 332, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 1962

Betty Brandt Notary Public.

My commission expires April 22, 1963



INVOICED
DATE 10/19/62
INV. NO. 5892-u

ROTARY DRILLERS LOG

OPERATOR: Petroleum, Inc. DRILLING COMMENCED: October 1, 1962
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: October 10, 1962
 El Dorado, Kansas

CASING RECORD: 284' - 8-5/8" surface LOCATION: Siefkes No. 1
 with 200 sacks cement SE SE SW
 Section 26-21S-12W
 Stafford County, Kansas

0 - 195 Sand
 195 - 291 Red beds
 291 - 1400 Shale
 1400 - 1657 Shale & lime
 1657 - 1870 Lime & shale
 1870 - 2020 Shale & lime
 2020 - 2140 Lime
 2140 - 2670 Shale
 2670 - 3090 Shale & lime
 3090 - 3247 Lime & shale
 3247 - 3497 Lime
 3497 - 3586 Lime & shale
 3586 - 3620 Shale & sand
 3620 - 3659 Lime & Rotary Total Depth

RECEIVED
 STATE CONSERVATION COMMISSION
 OCT 17 1962
 CONSERVATION DIVISION
 WICHITA, KANSAS

I hereby certify the foregoing statements are true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves
 John C. Graves President

STATE OF KANSAS)
) SS
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 16th day of October, 1962.

My commission expires April 22, 1963

Betty Brandt
 Betty Brandt Notary Public