


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Pawnee County, Sec. 33 Twp. 21 Rge. 16 (E) 16 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Sunray Mid-Continent Oil Company  
Lease Name Larned Unit #2 Well No. 1  
Office Address Box 788, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 30 19 53  
Application for plugging filed December 5 19 59  
Application for plugging approved December 7 19 59  
Plugging commenced December 12 19 59  
Plugging completed December 17 19 59  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August 1959  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Arbuckle Depth to top 3865 Bottom 3876 Total Depth of Well 3921 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	990	None
				5 1/2	3864	3383

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3915' and found it open. Filled with sand to 3828' and dumped 5 sacks cement plug from 3828' to 3786'. Shot off 5 1/2" casing and pulled 3383'. Pumped 76 bbls. mud and 80 sacks cement and squeezed to 300 psi. Cement plug from 266' to 20'. Mudded to 10', set rock bridge and ran 2 sacks cement to base of cellar.

Plugging Completed

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1960  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
I, C. H. Peterson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.H. Peterson  
Box 788, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January, 19 60

My commission expires December 24, 1960

Notary Public.



Sunray Oil Corporation  
Tulsa, Oklahoma

Tulsa, Oklahoma  
June 29, 1953

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: June 11, 1953  
Drilling Completed: June 25, 1953

Larned Unit 2-#1 N/2  
NE-NE-Section 33-21S-  
16W, Pawnee County,  
Kansas.

DRILLERS LOG

Sand	0-127
Shale and Clay	127-420
Sand	420-510
Red Bed	510-981
Anhydrite	981-1015
Shale & Shells	1015-1720
Shale & Lime	1720-1830
Lime	1830-1950
Shale & Lime	1950-2042
Lime	2042-2130
Lime & Shale	2130-2220
Shale & Lime	2220-2440
Lime & Shale	2440-2535
Shale & Broken Lime	2535-2690
Shale & Lime	2690-3155
Lime & Shale	3155-3368
Lime	3368-3859
Simpson	3859-3864
Arbuckle	3864- <del>3921</del> 3921 TD

I, Frank E. Stickle hereby certify the above to be a true and complete drillers log of Sunray Oil Corporation's Larned Unit #2-#1 N/2 NE-NE-Section 33-21S-16W, Pawnee County, Kansas.

*Frank E. Stickle*  
Frank E. Stickle

*Lillian T. Bonham*  
Notary Public

February 13, 1956  
My Commission Expires

RECEIVED  
STATE CORPORATION COMMISSION

JAN 8 1960

CONSERVATION DIVISION  
Wichita, Kansas