


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 33 Twp. 21 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Morgenstern & Specter, Inc.  
Lease Name Larned Townsite Unit #4 Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 7-8-56 19  
Application for plugging filed 10-17-60 19  
Application for plugging approved 10-18-60 19  
Plugging commenced 10-25-60 19  
Plugging completed 10-28-60 19  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot.  
Producing formation arbuckle Depth to top 3831 Bottom 3885 Total Depth of Well 3885 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	980'	None
				5-1/2"	3884'	3146'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3885', ran sand to 3875' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing. Pumped in 20 sacks of jell mud and 100 sacks of cement. Cement filled to 32'. Ran 10 sacks of cement to base of cellar.

NOV 21 1960  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING CO. (If additional description is necessary, use BACK of this sheet)  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1960

Milton J. Volin  
Notary Public.

My commission expires May 20, 1964



COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company: ROCKET DRILLING CO., INC.  
Farm: Earned Townsite No. 1  
Unit #4

SEC. 33 T. 21 R. 16W  
SW SE SW

Total Depth. 3888  
Comm. 6-22-56 Comp. 6-30-56  
Shot or Treated.  
Contractor. Rocket Drilling Co., Inc.  
Issued. 8-18-56

SEC. \_\_\_\_\_  
County Pawnee KANSAS



Elevation. 1997 RB

Production. 262 BOPD & NW

CASING:

8 5/8 985' w/ 410 sx cmt.  
5 1/2 3888' w/ 125 sx cmt.

Figures indicate Bottom of Formation.

sand	80
clay & sand	325
clay & shale	410
Dakota sand	520
shale	570
sand & shale	625
shale	977
anhydrite	1015
shale	1135
shale, salt & lime	1840
shale & lime	2005
lime	2010
sand	2020
lime	2175
sand	2190
lime	2345
lime & shale	2415
sand	2425
lime & shale	2475
shale	2700
lime & shale	2915
lime	3095
lime & shale	3563
Kansas City	3666
lime & shale	3783
shale	3837
Arbuckle	3888
Total Depth	

TOPS: (KBM)

Anhydrite	976
Heebner	3397
Brown lime	3495
Lansing	3504
Simpson	3828
Arbuckle	3837

RECEIVED  
STATE CORPORATION COMMISSION

OCT 14 1960

COMMISSION DIVISION