

1 070142

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C N/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,597.0000
NE SE, SEC. 9, T. 20 S, R. 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161
Operator: Palomino Petroleum
Name & Address: P. O. Box 18610
Wichita, KS 67218

2310 feet from S section line
660 feet from E section line
Lease Name Lowén Betz Well # 1
County Ness
Well Total Depth 4470 HS: 28 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 532

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 pm Day: 28 Month: February Year: 19 86

Plugging proposal received from Millard Kelso
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4469' PBD 4436' Perfs at 4405-15'
1st plug sand back to 4355' and dump 5 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 70 sx cement, 15
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 400 psi

Remarks: Recovered 2500' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging

RECEIVED STATE CORPORATION COMMISSION

Signed Dan Jordan (TECHNICIAN)

DATE MAR 12 1986

MAR 11 1986

INV. NO. 12947

3-11-86 CONSERVATION DIVISION
Wichita, Kansas