

1 030814

6-8-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5900

Operator: Lawbanco Drilling, Inc.
Name & Address P.O. Box 289
Natoma, KS 67651

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 506, Russell, KS

Company to plug at: Hour: 6 p.m. Day: 8 Month: 6 Year: 19 87

Plugging proposal received from Bill Owen

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2240'
Anhydrite 1366'

1st plug at 1350' with 60 sx cement, 2nd plug at 750' with 50 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 p.m. Day: 8 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1350' with 60 sx cement,

2nd plug at 750' with 50 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 6-12-87

INV. NO. 17226

API NUMBER 15- 145-21,260.0000
NE NE SE, SEC. 16, T 20 S, R 19 (W/K)

2310 feet from S section line

330 feet from E section line

Lease Name S.O.P. Sturgeon Well # 1

County Pawnee 141.38

Well Total Depth 4350 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 388

6-11-87

RECEIVED

STATE CORPORATION COMMISSION

JUN 11 1987

Signed Steve Durrant
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 5 month 1 day 87 year

API Number 15-145-21,260.0000

OPERATOR: License # 5900
Name Lawanco Drilling, Inc.
Address P.O. Box 289
City/State/Zip Natoma, Kansas 67651
Contact Person Reva F. Musgrove
Phone 913-885-4676

NE NE SE Sec. 16 Twp. 20 S, Rg. 19 West
2310 Ft. from South Line of Section
330 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 8241
Name Emphasis Oil Operations
City/State P.O. Box 506 Russell, Ks

Nearest lease or unit boundary line 330 feet
County Pawnee
Lease Name S.O.P. Sturgeon Well # 1
Ground surface elevation 2240 feet MSL
Domestic well within 550 feet yes no
Municipal well within one mile yes no
Surface pipe by Alternate 1-2
Depth to bottom of fresh water 100'
Depth to bottom of usable water 208' base K
Surface pipe planned to be set 350'
Projected Total Depth 4350 feet
Formation Mississippi

Well Drilled For: Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.
Date 4-14-87 Signature of Operator or Agent Title President

For KCC Use:
Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt.
This Authorization Expires 10-15-87 Approved By 4-15-87

Move in 6-1-87 8 1/2 @ 350'
PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, feet depth with, and size of plug. Includes entries for 1st through 5th plugs and Rathole/Mousehole.

Vertical list of well parameters:
PUSHER: Bill Jony
TD: 4350 FORMATION: Mississippi
SURFACE PIPE: 8 7/8 @ 388
ANHYDRITE: 1366 ELEVATION: 2240
STARTING TIME & DATE: 6:00 pm 6-8-87
COMPLETION TIME & DATE: 8:00 pm 6-8-87
1st PLUG @ 1350 FT. W/ 60 SX
2nd PLUG @ 750 FT. W/ 50 SX
3rd PLUG @ 390 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ NA SX
WATER WELL PLUGGED W/ Sand
CEMENT COMPANY: 6/406 b - 2 1/2 CB

TECHNICIAN: Halliborton
RECEIVED STATE CORPORATION COMMISSION
JUN 11 1987
CONSERVATION DIVISION
Wichita, Kansas