

1 090534

15.135.30077.0000

API NUMBER 15-11/70

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SW, SEC. 7, T 20 S, R 22 W/E

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8524

Lease Name McCreight C Well # 1

Operator: Jetgo Oil Company

County Ness 141.77

Name & Address P.O. Box 307

Well Total Depth 4362 feet

Jetmore, KS 67854-0307

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co., Inc. License Number

Address P.O. Box 420, Ness City, KS

Company to plug at: Hour: 10:45 a.m. Day: 5 Month: 4 Year: 19 95

Plugging proposal received from Mike

(company name) Allied (phone) 913-798-3843

were: 5 1/2" at 4354' w/100 sx cement, Open hole

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,

2nd plug perforate casing at 750' and pump in 80 sx cement,

3rd plug pull casing to 270' and pump 40 sx cement,

4th plug pull casing out and fill with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of sand through bailer,

2nd plug perforated casing at 750' and pumped in 80 sx cement. Casing parted at 217'

3rd plug pumped in 50 sx cement and circulated cement to surface.

4th plug pulled casing out of hole and topped off with 5 sx cement. Stayed full.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 217' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 4-25-95

INV. NO. 42690

RECEIVED STATE CORPORATION COMMISSION APR 14 1995 CONSERVATION DIVISION WICHITA, KANSAS

INVOICED