

To: 1 052083
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
136 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-145-20,607.0000

W/2 SW SE, SEC. 7, T 20 S, R 20 W/4
660 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30601

Lease Name Bayer Well # 1

Operator: Northstar Investments, Inc.

County Pawnee 143.65

Name: 13735 Pinnacle

Well Total Depth 4420 feet

Address

Conductor Pipe: Size feet

Wichita, KS 67230-1545

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Quality Well Service License Number 31925

Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 2 p.m. Day: 14 Month: 11 Year: 19 96

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-278-2476

were: 5 1/2" at 4414' with 75 sx cement, Perfs at 4376-80'

1st plug sand back to 4275' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1450' with 50 sx cement,

3rd plug at 550' with 50 sx cement,

4th plug at 275' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:20 p.m. Day: 14 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4261' and dumped 5 sx cement on top of sand through bailer,

2nd plug at 1430' with 50 sx cement,

3rd plug at 588' with 50 sx cement,

4th plug at 245' with 40 sx cement,

5th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 272' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
I (date) observe this plugging.

DATE NOV 21 1996

INV. NO. 47007

Signed Richard W. Lucy (TECHNICIAN)

11-14 JAN 28 1997