

15.145.20938.0000

1052362

TO: STATE CORPORATION COMMISSION API NUMBER 15-145-20,972- SW SE SE SEC. 7, T 20 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BAYER WELL # 3

TECHNICIAN'S PLUGGING REPORT 12/29 COUNTY PAWNEE 142.32

OPERATOR LICENSE # 30601 WELL TOTAL DEPTH 4379 FEET

OPERATOR: NORTHSTAR INVESTMENTS, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4357' WITH 125 SX

NAME AND 13735 PINNACLE SURFACE CASING: SIZE 8 5/8" @ 450' WITH 300 SX

ADDRESS WICHITA, KS 67230-1545

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 29 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4344-4352

1ST PLUG SAND TO 4290' OF 5 1/2" AND 5 SX CEMENT. SPOTTED PLUGS THROUGH CASING.

2ND PLUG AT 1350' WITH 200# HULLS - 7 SX GEL - 50 SX CEMENT - DISPLACED WITH 3 SX GEL.

3RD PLUG AT 480' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:50 PM DAY: 29 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4290' OF 5 1/2" AND 5 SX CEMENT. SPOTTED PLUGS THROUGH CASING.

2ND PLUG AT 1350' WITH 200# HULLS - 7 SX GEL - 50 SX CEMENT - DISPLACED WITH 3 SX GEL.

3RD PLUG AT 480' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1517' OF 5 1/2" CASING

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED DATE 1/11/00 INV. NO. 061104

SIGNED Richard W. Lacey (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JAN 10 2000 CONSERVATION DIVISION Wichita, Kansas