

To: 121022 3-20  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,804.0000  
E/2 SW SE, SEC. 7, T 20 S, R 20 W 8  
660 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30601

Lease Name Bayer Well # 2

Operator: Northstar Investments Inc.

County Pawnee 141.93

Name & Address 13735 Pinnacle

Well Total Depth 4367 feet

Wichita, KS 67230-1545

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Leiker Well Service Inc. License Number 30891

Address P.O. Box 1902, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 20 Month: 3 Year: 1995

Plugging proposal received from Dean Britting

(company name) Northstar Investments Inc. (phone) 316-733-8997

were: 5 1/2" at 4357' w/75 sx cement, Perfs at 4350-57'

1st plug through tubing pump 25 sx cement at 3717-3417'

2nd plug circulate cement from 1300' inside 4 1/2" liner through tubing,

3rd plug pump in 8 5/8" X 5 1/2" annulus-4 1/2" liner at 1200-0' with 30 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:40 p.m. Day: 20 Month: 3 Year: 1995

ACTUAL PLUGGING REPORT 1st plug ran tubing inside of 4 1/2" & 5 1/2" to 3717' and spotted 25  
sx cement,

2nd plug pulled tubing to 1280' and circulated cement with 130 sx cement,

3rd plug pulled all tubing and topped off 4 1/2" casing with 10 sx cement,

4th plug pumped in 5 1/2" X 8 5/8" annulus with 5 sx cement. Shut in at 400 psi.

Dry cement was found in bradenhead before cementing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

**INVOICED** (If additional description is necessary, use BACK of this form.)  
observe this plugging.

DATE 3-30-95

Signed Dean Rankin  
(TECHNICIAN)

INV. NO. 42494