

To: 1 030833  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-19-87  
API NUMBER 15- 145-21,261.0000  
SE NW NW, SEC. 9, T 20 S, R 19 W/E  
4290 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3455

Lease Name Ellis Well # 1

Operator: Carmen Schmitt

County Pawnee 143.00

Name: Carmen Schmitt

Well Total Depth 4400 feet

Address 14 Circle Drive

Conductor Pipe: Size \_\_\_\_\_ feet

Beloit, KS 67420

Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 19 Month: 7 Year: 19 87

Plugging proposal received from Jerb Ogle

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2231'

Anhydrite 1428'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 750' with 75 sx cement

3rd plug at 30' below base of surface pipe with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:40 p.m. Day: 19 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1428' with 50 sx cement,

2nd plug at 750' with 75 sx cement

3rd plug at 262' with 40 sx cement,

4th plug at 0-40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 21 1987  
7-21-87  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby/ will not reserve this plugging.

Signed Steve Durrant  
(TECHNICIAN)

DATE 7-22-87

INV. NO. 17600 7-19

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

# NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date July 6, 1987  
month day year

API Number 15-145-21261-2

OPERATOR: License # 3455  
Name Carmen Schmitt  
Address 14 Circle Drive  
Beloit, KS 67420  
Contact Person Carmen Schmitt  
Phone 913-738-8210

SE NW NW Sec 9 Twp 20 Rg 19W  
4290 Ft. from South Line of Section  
4290 Ft. from East Line of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302  
Name Red Tiger Drilling Co.  
City/State Wichita, KS 76 67602

Nearest-lease or unit boundary line 990 feet  
County Ellis

Well Drilled For  
 Oil  SWD  Infield  Pool Ext.  Wildcat  
 Gas  Inj  Air Rotary  
 OWWO  Expl

Lease Name Ellis  
Ground surface elevation 500 feet MSL  
Domestic well within 350 feet X yes X no  
Municipal well within one mile X yes X no  
Surface pipe by Alternate: 350 Dakota  
Depth to bottom of fresh water 500 Cheyenne  
Depth to bottom of usable water 205  
Surface pipe planned to be set 4450 feet  
Formation Mississippian

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date  
Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.  
cementing will be done immediately upon setting production casing.  
Date 7-1-87 Signature of Operator or Agent Carmen Schmitt Title

For KCC Use:  
Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. X  
This Authorization Expires 1-6-88 Approved By RTH 7-6-87

*None in 1-10-87 898-2151 slw*

## PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @	1500	feet depth with	20	sxs of
2nd plug @	600	feet depth with	100	sxs of
3rd plug @	250	feet depth with	40	sxs of
4th plug @	40	feet depth with	10	sxs of
5th plug @		feet depth with		sxs of
(2) Rathole with	10	sxs		(b) Mousehole with

PUSHER	<u>Jack Ogle</u>
TD	<u>4400</u> FORMATION
SURFACE PIPE	<u>8 7/8 @ 232</u>
ANHYDRITE	<u>1428 base</u> ELEVATION <u>2221</u>
STARTING TIME & DATE	<u>Apr 7-1987</u>
COMPLETION TIME & DATE	<u>8:40</u>
1st PLUG @	<u>1428</u> FT. W/ <u>50</u> SX
2nd PLUG @	<u>150</u> FT. W/ <u>15</u> SX
3rd PLUG @	<u>262</u> FT. W/ <u>40</u> SX
4th PLUG @	<u>0-40</u> FT. W/ <u>10</u> SX
RAT HOLE CIRCULATED W/	<u>15</u> SX
MOUSE HOLE CIRCULATED W/	<u>—</u> SX
WATER WELL PLUGGED W/	<u>—</u> SX
CEMENT COMPANY	<u>Allied</u>
TECHNICIAN	<u>6940 698</u>

STATE OF KANSAS  
JUL 21 1987  
CONSERVATION DIVISION  
Wichita, Kansas