

1 080489

261 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,239.0000  
NW SW NE, SEC. 9, T 20 S, R 19 W/EX  
3630 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Ellis Well # 1

Operator: Energy Three, Inc.

County Pawnee 141.77

Name & Address P. O. Box 1505

Well Total Depth 4362 Mississippi feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Big Three Drilling Co., Inc. License Number 5836

Address P. O. Box 52, Gorham, KS 67640

Company to plug at: Hour: 4:00 am Day: 21 Month: February Year: 19 86

Plugging proposal received from Stan Lovelady

(company name) Big Three (phone) 913-637-5487

Elevation 2250'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1398' top

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 500' with 50 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with

10 sx cement Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:15 am Day: 21 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1436' with 50 sx cement, 2nd plug at 810' with 50  
sx cement, 3rd plug at 290' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 26 1986

INV. NO. 12695

RECEIVED Signed  
STATE CORPORATION COMMISSION

FEB 24 1986 2-24-86

(TECHNICIAN)

CARD MUST BE TYPED

State of Kansas

15.145.21239.0000

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

2

Starting Date FEBRUARY 10 1986  
month day year

API Number 15- 145-21,239

OPERATOR: License # 5130  
Name ENERGY THREE, INC.  
Address P.O. Box 1505  
City State Zip GREAT BEND, KANSAS 67530  
Contact Person CHARLES DIXON  
Phone AC316-792-5968

NW SW NE Sec 9 Twp 20 S. Rg 19 East  
2630 Ft. from South Line of Section  
2310 Ft. from East Line of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5836  
Name B.I.G. THREE DRILLING CO. INC.  
City/State BOX 52, GOHHAM, KS 67540

Nearest lease or unit boundary line 200 feet  
County RAYNEE  
Lease Name ELLIS Well # 1  
Ground surface elevation 2252 feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Surface pipe by Alternate: 1 2 X 0  
Depth to bottom of fresh water  
Depth to bottom of usable water 450  
Surface pipe planned to be set 200' AT 2  
Projected Total Depth 4350 feet  
Formation CHEROKEE SAND

Well Drilled For: Well Class: Type Equipment:  
X Oil SWD Infield X Mud Rotary  
Gas Inj Pool Ext Air Rotary  
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator  
Well Name  
Camp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.  
Date 2-7-86 Signature of Operator or Agent Title EXEC. VICE-PRESIDENT

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. A 2  
This Authorization Expires 2-10-86 Approved By 2-10-86

2-13-250 8/8

RECEIVED  
STATE CORPORATION COMMISSION

FEB 24 1986

CONSERVATION DIVISION  
Wichita, Kansas