

12-27

To: 1 031054
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,297-0000
NW SE NE, SEC. 9, T 20 S, R 19 W/E
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9971
Operator: Kodiak Petroleum, Inc.
Name & Address 44 Inverness Drive East, Bldg. D
Englewood, CO 80112

Lease Name Ellis Well # 9-8
County Pawnee 81.25
Well Total Depth 2500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 463

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Company License Number _____

Address P.O. Box 31, Russell, KS 67665

Company to plug at: Hour: 11 a.m. Day: 27 Month: 12 Year: 19 89

Plugging proposal received from Harvey Moore

(company name) Kodiak Petroleum (phone) 913-628-6043

were: 4 1/2" at 2500' PBTD 2365' Perfs at 2325-31', 2344-49' TOC 1900'

1st plug sand back to 2275' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 27 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 2275' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1990 12-28-89

Maximum pressure 800 psi and shut in 400 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1867' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-5-90

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 26892

12-27 FEB 28 1990