

1090164

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,021

C NW NE , SEC. 8 , T 20 S, R 20

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Fox Well # A-1

Operator: Pickrell Drilling

County Pawnee

Name & Address Litwin Building, Suite 205

Well Total Depth 4357 141.60 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 17 Month: May Year: 19 84

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-692-2506

were: 5 1/2 set at 4356 PBD 4200 Perfs 4136-38

1st plug sand back to 4075 and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, and 150 sx cement

Maximum pressure 700# and shut in pressure 400#

Plugging Proposal Received by R. B. Arbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X _____ None _____

Operations Completed: Hour: 11:40 am Day: 17 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4356' PBD 4200' Perfs 4136-38

1st plug sand back to 4075 and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel and 150 sx cement

Maximum pressure 700# and shut in pressure 400#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied

(If additional description is necessary, use BACK of this form.)

(did / observe) observe this plugging.

INVOICED

DATE 5-25-84

INV. NO. 1672

S-17

Signed R. B. Arbutton
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1984
CONSERVATION DIVISION
Wichita, Kansas