

To: 1 120623
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8902
Operator: Sam Mays
Name & Address P.O. Box 62
Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 16 Month: 9 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" set at 4339' w/75 sx cement, Open hole
1st plug sand back to 4280' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 16 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4280' and dumped 5 sx cement
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement. RECEIVED
Pumping pressure 0-900 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2400' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (or ~~we~~) observe this plugging.

DATE 10-18-91
WV. NO. 33391

Signed [Signature]
(TECHNICIAN)

SEP 18 1991

CONSERVATION DIVISION
WICHITA, KANSAS