

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145 - 20,413-A
NE NE, Sec. 8, T 20 S, R 20 W/X
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L. D. Davis
Name & Rt. 1, Box 183B
Address Great Bend, KS 67530

Lease Name Fox "A" Well # 1
County Pawnee
Well Total Depth 4336 feet 140.92
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling License Number 6039

Address Rt. 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 2 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO _____

(company name) L.D. Davis (phone) 316-793-3051

were: 4 1/2" set at 4323 PBTB 4310' Perfs 4304 - 08 4301 - 03

1st plug pumped 1 sx hulls, 25 sx cement, 20 sx gel and 100 sx cement down 4 1/2

2nd plug pumped 200 sx cement down anulus

Shut-in pressure - 1st plug 2300#

Shut-in pressure - 2nd plug 800#

Signed Steve Krumm
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:30 pm Day: 2 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4323 PBTB 4310' Perfs 4304-08 4301-03

1st plug pumped 1 sack hulls, 25 sx cement, 20 sx gel and 100 sx cement down 4 1/2"

Shut-in pressure 2300#

2nd plug pumped 200 sx cement down anulus Shut-in pressure 800#

Remarks: 60/40 Pozmix 2% gel 3% cc by Halliburton

No recovery

STATE CORPORATION COMMISSION
RECEIVED
MAR 07 1984 3/7/84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated
and that I (did / ~~did not~~) observe this plugging.

Signed Steve Krumm
(TECHNICIAN)

INVOICED

DATE 3-9-84

INV. NO. 0670 3-2