

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02727-00-00
 Spot: SENWSE Sec 33 Twp 16 S Rng 23 E / W
1586 Feet from N / S Line of Section
1956 Feet from E / W Line of Section
 GPS: Lat: 38.611249 Long: 94.870659 Date: 2/6/17 2/6/16
 Lease Name: Hendrickson-Edwards (Hendrickson) Well #: HDN 08
 County: Miami Total Vertical Depth: 310 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>8.000</u>	<u>15</u>	<u>0</u>	<u>EST</u>
Address 1: <u>266 N. Main St. Ste. 266</u>	<u>L1 - Liner 1</u>	<u>6.250</u>	<u>200</u>	<u>0</u>	<u>EST</u>
Address 2: _____	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>310</u>	<u>0</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (Oil) UIC Docket No.: _____ Date/Time to Plug: 1/13/17 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 1/13/17 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Clear around well location. Run 1" and reamer to 300 ft. Pull out. Perforate well. Run 1" to 300 ft. Wash to 310 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 26 sacks of cement. Well plugged.		<u>100</u>	<u>250</u>	<u>TBG - Tubing</u>

Remarks: Contract # 41035. Control # 201600008-008. GPS'ed NAD 83 by FG and TH. Reg Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03
 RECEIVED
 KANSAS CORPORATION COMMISSION
Frank Guilfoyle
 (Technician)
 Form: District Plugging Report - _____
 MAR 02 2017
 CONSERVATION DIVISION
 WICHITA, KS