

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02728-00-00
 Spot: NE SW NW SE Sec 33 Twp 16 S Rng 23 E / W
2009 1701 Feet from N / S Line of Section
2214 2229 Feet from E / W Line of Section
 GPS: Lat: 38.611571 Long: 94.871618 Date: 2/17/17 2/17/16
 Lease Name: Hendrickson-Edwards (Hendrickson) Well #: HDN 21
 County: Miami Total Vertical Depth: 285 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>7.000</u>	<u>20</u>	<u>0</u>	
Address 1: <u>266 N. Main St. Ste. 266</u>	<u>PROD - Casing</u>	<u>2.000</u>	<u>285</u>	<u>0</u>	
Address 2: _____	<u>T1 - Tubing 1</u>	<u>1.000</u>	<u>275</u>	<u>275</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (-Oil) UIC Docket No.: _____ Date/Time to Plug: 1/4/17 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 1/4/17 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
<p>Clear trees around location. Pull on 1" pipe. Pump hung. Work loose. Pull 275 ft of 1" out. Run 1" in to 275 ft. Wash to 285 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 20 sacks of cement. Well plugged.</p>				

Remarks: Control No. 20160008-021. Contract No. 41035. GPS NAD 83 by FG and TH. Reg Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03
RECEIVED
 KANSAS CORPORATION COMMISSION
 MAR 02 2017
 CONSERVATION DIVISION
 WICHITA, KS
Frank Guilfoyle
 (Technician)
 Form: District Plugging Report - _____