

API Well Number: 15-121-02707-00-00
 NE Spot: SESWSE Sec 33 Twp 16 S Rng 23 E / W
372 Feet from N / S Line of Section
1642 Feet from E / W Line of Section
 GPS: Lat: 38.607910 Long: 94.869524 Date: 4/16/17 4/4/16
 Lease Name: Hendrickson-Edwards (Edwards) Well #: EDW 09
 County: Miami Total Vertical Depth: 310 feet

Kansas Corporation Commission
District Plugging Report

Operator License No: 101
 Op Name: STATE OF KANSAS
 Address 1: 266 N. Main St. Ste. 266
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

| String | Size | Depth | Pulled | Comments |
|---------------------------|--------------|------------|------------|----------------------|
| <u>DRIVE - Drive Pipe</u> | <u>8.000</u> | <u>12</u> | <u>0</u> | <u>EST</u> |
| <u>T1 - Tubing 1</u> | <u>6.250</u> | <u>250</u> | <u>0</u> | <u>EST</u> |
| <u>T2 - Tubing 2</u> | <u>1.000</u> | <u>310</u> | <u>260</u> | <u>1" rotted off</u> |

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: _____ Date/Time to Plug: 2/16/17 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Recvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report:
 Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 2/16/17 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:

| Perfs: | Top | Bottom | Thru |
|--|-----------|------------|---------------------|
| | <u>75</u> | <u>250</u> | <u>TBG - Tubing</u> |
| Clear junk from location. Pull 260 ft of 1" from well. The 1" rotted off. Run 1" and swedge to 250 ft to make sure there was no 2" pipe in well. Perforate well. Run 1" to 310 ft and hit hard. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 91 sacks of cement. Well plugged. | | | |

Remarks: Control No. 20160008-033. Contract No. 41035. GPS NAD 83 by FG. Reg Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 KCC WICHITA Frank Guilfoyle
 (Technician)
 APR 05 2017 Form: District Plugging Report -
 RECEIVED