

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-121-02712-00-00  
 Spot: SESWSE Sec 33 Twp 16 S Rng 23  E /  W  
622 Feet from  N /  S Line of Section  
1611 Feet from  E /  W Line of Section  
 GPS: Lat: 38.608596 Long: 94.869423 Date: 4/4/17  
 Lease Name: Hendrickson-Edwards (Edwards) Well #: EDW 10  
 County: Miami Total Vertical Depth: 350 feet

Operator License No: 101  
 Op Name: STATE OF KANSAS  
 Address 1: 266 N. Main St. Ste. 266  
 Address 2:  
 City: WICHITA  
 State: KS Zip Code: 67202 - 1513  
 Well Type: OG - Oil & Gas (Oil)  
 Plug Co License No.: 33749  
 Proposal Rcvd from: Mike Kepley  
 String: DRIVE - Drive Pipe Size: 8.000 Depth: 15 Pulled: 0 Comments: EST  
T1 - Tubing 1 Size: 6.250 Depth: 350 Pulled: 0 Comments: EST  
 UIC Docket No.: Date/Time to Plug: 2/17/17  
 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 2/17/17 KCC Agent: Frank Guilfoyle  
 Actual Plugging Report: 2/17/17

Perfs:	Top	Bottom	Thru
	<u>75</u>	<u>250</u>	<u>TBG - Tubing</u>
Clear trees and trash from location. Run 1" and swedge to 250 ft. Pull out. Perforate pipe. Run 1" to 325 ft and wash to 350 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 117 sacks of cement. Well plugged.			

Remarks: Control No. 20160008-034. Contract No. 41035. GPS NAD 83 by FG. Reg Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
 KCC WICHITA  
 APR 05 2017  
 RECEIVED  
Frank Guilfoyle  
 (Technician)  
 Form: District Plugging Report -