

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-121-02723-00-00  
 Spot: NESWSE Sec 33 Twp 16 S Rng 23  E /  W  
1284 Feet from  N /  S Line of Section  
1563 Feet from  E /  W Line of Section  
 GPS: Lat: 38.610410 Long: 94.869280 Date: 1/2/18 1/2/18  
 Lease Name: Hendrickson-Edwards (Edwards) Well #: EDW 15  
 County: Miami Total Vertical Depth: 330 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>T1 - Tubing 1</u>	<u>4.500</u>	<u>330</u>	<u>0</u>	
Address 1: <u>266 N. Main St. Ste. 266</u>	<u>L2 - Liner 2</u>	<u>2.000</u>	<u>310</u>	<u>310</u>	
Address 2:	<u>T3 - Tubing 3</u>	<u>1.000</u>	<u>310</u>	<u>310</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 12/14/16 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 12/14/16 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Clear trees around well. Try to pull 1" out. Stuck inside 2". Work on getting 1" loose. Pull 1" apart. Pull out. Pull 2" out. Perforate 4.5". Run 1" and wash to 330 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 39 sacks of cement. Well plugged.		<u>75</u>	<u>250</u>	<u>TBG - Tubing</u>

Remarks: Control No. 20160008-039. Contract No. 41035. GPS NAD 83 by FG. Reg Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03

KCC WICHITA

JAN 05 2018

RECEIVED

Frank Guilfoyle  
 (Technician)

Form: District Plugging Report -