

API Well Number: 15-121-02711-00-00
 NW Spot: SWSESE Sec 33 Twp 16 S Rng 23 E / W
573 Feet from N / S Line of Section
1277 Feet from E / W Line of Section
 GPS: Lat: 38.608454 Long: 94.868251 Date: 2/17 2/1/16
 Lease Name: Hendrickson-Edwards (Edwards) Well #: EDW 22
 County: Miami Total Vertical Depth: 310 feet

Kansas Corporation Commission
District Plugging Report

Operator License No: 101
 Op Name: STATE OF KANSAS String T1 - Tubing 1 Size 2.000 Depth 310 Pulled 0 Comments
 Address 1: 266 N. Main St. Ste. 266 String T2 - Tubing 2 Size 1.000 Depth 300 Pulled 300
 Address 2:
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: Date/Time to Plug: 12/23/16 /
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
 Plugging
 Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 12/23/16 / KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Pull 1" and pump out. Perforate well. Run 1" to 300 ft. Wash inside to 310 ft and hit. Pump Portland cement to surface inside and outside. Had to break up cement around 2" to get circulation on back side of 2". Pull pipe and top off well. Pump total of 65 sacks of cement. Well plugged.		<u>75</u>	<u>250</u>	<u>TBG - Tubing</u>

Remarks: Control No. 20160008-046. Contract No. 41035. GPS NAD 83 by FG. Reg Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 **KCC WICHITA**
FEB 03 2017
RECEIVED
Frank Guilfoyle
 (Technician)
 Form: District Plugging Report -