

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21673-00-00
Spot: E2E2NWSW Sec/Twnshp/Rge: 27-27S-18W
1980 feet from S Section Line, 1300 feet from W Section Line
Lease Name: ANTHONY Well #: 1-27
County: KIOWA Total Vertical Depth: 4880 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4878	2500	WITH 275 SX CMT
SURF	8.625	480		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2015 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 4736' WITH 5 SX CMT. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2015 1:45 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SANDED BACK TO 4736' WITH 5 SX CMT. 1ST PLUG AT 1230' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 548' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4790	4808		
4770	4790		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Larry Harris
(TECHNICIAN)

1-19-18
RECEIVED
JAN 19 2018
KCC DODGE CITY