

1051980

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 145-20,907.0000  
SE SE NE, SEC. 14, T 20 S, R 17 W XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419  
Operator: Bear Petroleum, Inc.  
Name & Address: P.O. Box 438  
Haysville, KS 67060

2970 feet from S section line  
330 feet from E section line  
Lease Name Seeman Well # 1  
County Pawnee 126.75  
Well Total Depth 3900 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gressel Oil Field Service, Inc. License Number 3009  
Address P.O. Box 607, Burrton, KS 67020

Company to plug at: Hour: 9 a.m. Day: 7 Month: 11 Year: 1995  
Plugging proposal received from Dick Schremmer  
(company name) Bear Petroleum (phone) 316-524-1225

Work: 4 1/2" at 3900' with 100 sx cement, PBD 3880', Perfs at 3872-76'  
1st plug sand back to 3820' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:15 a.m. Day: 7 Month: 11 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 3820' and dumped 4 sx cement on top of sand through bailer,  
2nd plug pumped down the 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 1000 psi and shut in 50 psi.

STATE CORPORATION COMMISSION RECEIVED

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1200' of 4 1/2" casing. 11/14/95

INVOICED  
If additional description is necessary, use BACK of this form.  
I (and my MINOR) observe this plugging.

DATE 11-16-95  
INV. NO. 44036  
11-7

Signed Richard M. Lacy (TECHNICIAN)