

1 050866

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,253.0000
SW NE SW, SEC. 4, T 20 S, R 19 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6420
Operator: K.R.M. Petroleum Corporation
Name & Address 1900 Grand Street, Suite 300
Denver, CO 80203

Lease Name Smith Well # 1-4
County Pawnee 140.40
Well Total Depth 4320 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Revlin Drilling Inc. License Number 5671

Address Box 293, Russell, KS 67665

Company to plug at: Hour: 8 a.m. Day: 1 Month: 1 Year: 19 87

Plugging proposal received from Paula Gibson

(company name) Revlin Drilling Inc. (phone) 913-483-5355

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2233'
Anhydrite 1388'

1st plug at Base Anhydrite with 50 sx cement,

2nd plug at 700' with 50 sx cement, 3rd plug at 480' with 50 sx cement,

4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi & Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:15 a.m. Day: 1 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1414' with 50 sx cement,

2nd plug at 700' with 50 sx cement,

3rd plug at 480' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION
1-6-87
JAN 8 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 1-7-87

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 15820

1-1

2233
1983

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

Starting Date 12 16 1986
month day year 350

API Number 15-145-21-253.0000

OPERATOR: License # 6420
Name K.R.M. Petroleum Corporation
Address 1900 Grand Street, Suite 300
City/State/Zip Denver, CO 80203
Contact Person James Catlin
Phone 303.830.6601

SW NE SW Sec 4 Twp. 20 S, Rg. 19
1650 Ft. from South Line of Section
3630 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5671
Name Revlin Drilling Inc.
City/State Box 293, Russell, KS 67665

Nearest lease or unit boundary line 990 feet
County Pawnee

Well Drilled For: Well Class: Type Equipment:
X Oil SWD X Infield XMud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name Smith Well # 1-4
Ground surface elevation 2233 feet MSL

If OWWO: old well info as follows:

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Operator
Well Name
Comp Date Old Total Depth

Depth to bottom of fresh water 75
Depth to bottom of usable water 400

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 440

Date 12/15/86 Signature of Operator or Agent *Clarence Barkman* Title as agent

Conductor pipe required
Projected Total Depth 4350 feet

For KCC Use:

Formation Cherokee

Conductor Pipe Required feet; Minimum Surface Pipe Required 440 feet per Alt. 1 of

This Authorization Expires 6-15-87 Approved By 12-15-86

Set 440' of 8 3/8 on 12-22-80

AMS/White

SW NE SW Sec 4 Twp. 20 S, Rg. 19 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1360 feet depth with 50 sxs of 60-40 poz. 2% gel.
2nd plug @ 500 700 feet depth with 50 sxs of 60-40 poz. 2% gel.
3rd plug @ 40 wiper plug feet depth with 10 sxs of 60-40 poz. 2% gel.
4th plug @ 500 480 feet depth with 10 sxs of
5th plug @ 40 feet depth with 10 sxs of

(2) Rathole with 15 sxs

PUSHEX Barkman w/ Revlin
TD 4720 FORMATION *Cher*
SURFACE PIPE 8 3/8 @ 450
ANHYDRITE 1388 Top ELEVATION 2233
STARTING TIME & DATE 8:00 on 1-1-86
COMPLETION TIME & DATE 10:15 on 1-1-86
1st PLUG @ 1414 FT. W/ 50 SX
2nd PLUG @ 700 FT. W/ 50 SX
3rd PLUG @ 480 FT. W/ 50 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY *Allied*
TECHNICIAN *Lacey*

STATE CORPORATION COMMISSION

JAN 6 1987

CONSERVATION DIVISION
Wichita, Kansas