

1050423

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,163-0000

SE SE SW, SEC. 16, T 20 S, R 18 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Giles Well # 1

Operator: Frontier Oil Company  
Name & Address: 1720 Kansas State Bank Building  
Wichita, KS 67202

County Pawnee 135.20

Well Total Depth 4160 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 294 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 3 Month: January Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4159' Perfs at 4080-84'

1st plug sand back to 4030' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 pm Day: 3 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 4 1/2" set at 4159' Perfs at 4080-84'

1st plug sanded back to 4030' and dumped 4 sx cement on top of sand through bailer,  
2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 700 psi and shut in 400 psi

Remarks: Recovered 2400' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(if additional description is necessary, use BACK of COPY of Form 1000  
Wichita, Kansas

I did observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

DATE 1-16-85  
6516

REV NO.