

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-20002-00-01  
Spot: NWSW Sec/Twnshp/Rge: 2-33S-31W  
2043 feet from S Section Line, 4552 feet from E Section Line  
Lease Name: HEADRICK OWWO Well #: 2  
County: SEWARD Total Vertical Depth: 5945 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3000		WITH 2 SX CMT
CIBP		5800		
PROD	4.5	5954	0	WITH 225 SX CMT
SURF	8.625	1300		WITH 500 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2017 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: OCTAVIO D MORALES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP @ 3300' WITH 2 SX CMT. PRESSURE TEST CASING TO 300#. PERFORATE AT 1350' THEN PUMP 50 SX CMT & 100# HULLS IN LAST HALF. PERFORATE AT 550' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: HEITH WALSH WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/18/2017 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 3000' WITH 2 SX CMT. PERFORATE AT 1350' WITH 50 SX CMT & 100# HULLS. PERFORATE AT 550' WITH 225 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
3030	3064		

INVOICED  
JAN 18 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Kenny Sullivan*  
512  
(TECHNICIAN)

RECEIVED  
DEC 21 2017  
KCC DODGE CITY