

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25983-00-00
Spot: SESWSWNE Sec/Twnshp/Rge: 27-20S-22W
2560 feet from N Section Line, 2200 feet from E Section Line
Lease Name: W-D 27 UNIT Well #: 1
County: NESS Total Vertical Depth: 4355 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/16/2017 3:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Revd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1420' WITH 50 SX CMT. 2ND PLUG AT 610' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD WitnessType: NONE
Date/Time Plugging Completed: 12/16/2017 5:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

1ST PLUG AT 1420' WITH 50 SX CMT. 2ND PLUG AT 610' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT.

Plugged through: DP

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
DEC 28 2017
KCC DODGE CITY

INVOICED
JAN 13 2018