

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-21194-00-00
Spot: SENSWSWE Sec/Twnshp/Rge: 27-17S-10W
915 feet from S Section Line, 2170 feet from E Section Line
Lease Name: SCHEPMANN Well #: 5-27
County: ELLSWORTH Total Vertical Depth: 3410 feet

Operator License No.: 33770
Op Name: ARES ENERGY, LTD
Address: 405 N. MARIENFELD SUITE 250
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3408		125 SX
SURF	8.625	363		195 SX
T1	2.375	3352		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2017 4:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY Company: ALLIANCE Phone: (432) 685-1960

Proposed Plugging Method: As required by KCC

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/19/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Set - CIBP @ 3278' w/ 2 sxs cmt on top. Circulated mud. Cut and pull casing @ 1340'. Spotted 35 sxs cement w/ 100 lbs of hulls & 3% cc @ 1310'. Went to tag plug and was not there. Respotted 35 sxs cement w/ 3% CC @ 1310' and tagged plug @ 1250'. Spotted 35 sxs @ 950' (top @ 800') pumped 100 sxs from 450' and did not circulate to surface, ran out of cement. 9/20/17, tagged plug @ 200'. Filled surface casing with 80 sxs from 200' to surface.

Perfs:

Top	Bot	Thru	Comments
3338	3344		
3326	3334		

INVOICED
JAN 16 2018

Remarks:

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)



1/8