

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-069-20295-00-00
Spot: SWSW Sec/Twnshp/Rge: 7-27S-30W
661 feet from S Section Line, 4599 feet from E Section Line
Lease Name: NALLY LAND AND CATTLE C Well #: 1-7
County: GRAY Total Vertical Depth: 2736 feet

Operator License No.: 33989
Op Name: BENGALIA LAND AND CATTLE COMP
Address: PO BOX 521008
TULSA, OK 74152

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2730	0	WITH 575 SX CMT
SURF	8.625	930		WITH 425 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/14/2017 9:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: DAVID HULLUM Company: BENGALIA LAND & CATTLE Phone: (918) 587-8022

Proposed Plugging Method: PUMP BOTTOM WITH 50 SX CMT & 200# HULLS. PULL TBG TO 1850' & PUMP 25 SX CMT. PULL TBG TO 1000' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2017 12:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMPED BOTTOM WITH 50 SX CMT & 200# HULLS. PULLED TBG TO 1866' & PUMPED 25 SX CMT. PULLED TBG TO 980' & CIRCULATED CMT TO SURFACE WITH 80 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. FILLED ANNULUS WITH 30 SX CMT. PRESSURED TO 1500 PSI.

Perfs:

Top	Bot	Thru	Comments
2663	2671		
2633	2671		

INVOICED
JAN 16 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

12-21-17
RECEIVED
DEC 21 2017
KCC DODGE CITY [Signature]

JA