

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-22391-00-00  
Spot: E2NWNWNE Sec/Twnshp/Rge: 29-6S-18W  
330 feet from N Section Line, 2240 feet from E Section Line  
Lease Name: BIGGE B Well #: 1  
County: ROOKS Total Vertical Depth: 3557 feet

Operator License No.: 3956  
Op Name: BRUNGARDT OIL AND LEASING INC.  
Address: 213 W. 7TH STREET PO BOX 871  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3557		165 SX
SURF	8.5	931		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2017 11:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: CHRISTOPHER BRUNGARD Company: BRUNGARDT OIL AND LEASING I Phone: (785) 483-4975

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 12 sx gel and 300 # hulls.  
F.O. Tool set at 1618'.  
Production perforations: 3311' - 3414'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2017 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2' casing and pumped 50 sx cement w/250 # hulls. Then pumped 12 sx gel followed by 160 sx cement. Pressured to 1000 psi. Hooked to 8 5/8" x 5 1/2" annulus and immediately pressured to 300 psi.

GPS: 39.50889N -099.35015W

Perfs:

Top	Bot	Thru	Comments
3411	3414		
3371	3375		
3327	3330		
3312	3317		
3311	3317		

INVOICED  
JAN 13 2018

Remarks: QUALITY OILWELL CEMENTING TICKET # 563

Plugged through: CSG

District: 04

Signed

Pat Bedore

KCC WICHITA

(TECHNICIAN)

CM

DEC 20 2017

JAN 02 2018

RECEIVED

Form CP-2/3