

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23627-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 13-7S-24W  
2010 feet from N Section Line, 580 feet from E Section Line  
Lease Name: COUEY UNIT Well #: 5-13  
County: GRAHAM Total Vertical Depth: 3970 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3964		225 SX
SURF	8.625	207		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/20/2017 10:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.  
Port Collar at 2149' w/200 sx cement.  
Perforations: 3718' - 3720' and 3846' - 3850'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/20/2017 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/300 # hulls, followed by 10 sx gel, followed by 230 sx cement. Shut in pressure 500 psi. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 200 psi.

GPS: 39.44559 -099.94029

Perfs:

Top	Bot	Thru	Comments
3846	3850		
3718	3720		

INVOICED  
JAN 16 2018

Remarks: GLOBAL CEMENT TICKET # 3231

Plugged through: CSG

District: 04

Signed *Marvin Mills*  
KCC WICHITA (TECHNICIAN) CM

JAN 02 2018

RECEIVED

DEC 22 2017