

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23342-00-00
Spot: NWSEWNW Sec/Twnshp/Rge: 1-7S-24W
850 feet from N Section Line, 1840 feet from E Section Line
Lease Name: GRIDLEY TRUST Well #: 1-1
County: GRAHAM Total Vertical Depth: 4008 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4005		240 SX
SURF	8.625	289		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2017 2:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.
Port Collar at 2172' w/180 sx cement.
Perforations: 3886' - 3888'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2017 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/300 # hulls, followed by 10 sx gel, followed by 220 sx cement. Shut in pressure 400 psi. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.47791 -099.94450


Perfs:

Top	Bot	Thru	Comments
3886	3888		

Remarks: GLOBAL CEMENT TICKET # 3232

Plugged through: CSG

District: 04

Signed 
KCC WICHITA (TECHNICIAN) CM

JAN 02 2018

RECEIVED

DEC 22 2017

Form CP-2/3

INVOICED
JAN 13 2018