

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21551-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 18-22S-23W
4783 feet from S Section Line, 1964 feet from E Section Line
Lease Name: REED E Well #: 1
County: HODGEMAN Total Vertical Depth: 4731 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1736		CEMENTED WITH 350 SX CMT. CMT CIRCULATED.
PROD	5.5	4728	0	WITH 250 SX CMT
SURF	8.625	278		WITH 175 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/12/2017 1:00 PM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Revd. from: MARK LEIKER

Company: BEREXCO LLC

Phone: (316) 265-3311

Proposed
Plugging
Method:

MIX 50 SX CMT & 150# HULLS. SPACER TO 1750'. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 12/12/2017 4:00 PM

KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

PUMP BOTTOM WITH 50 SX CMT & 150# HULLS IN THE LAST 25 SX CMT. SPACER TO 1750'. CIRCULATED CMT TO SURFACE WITH 155 SX CMT. FILLED ANNULUS WITH 7 SX CMT.

Top	Bot	Thru	Comments
4708	4724		MISSISSIPPIAN

INVOICED
JAN 13 2018

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: CSG

District: 01

12/21/17
RECEIVED
DEC 21 2017
KCC DODGE CITY

Signed: [Signature] ECLS
(TECHNICIAN)
SA