

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21589-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 8-22S-23W
344 feet from S Section Line, 4944 feet from E Section Line
Lease Name: ABBIE Well #: 1
County: HODGEMAN Total Vertical Depth: 4904 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1715		WITH 350 SX CMT
PROD	5.5	4902	0	WITH 275 SX CMT
SURF	8.625	221		WITH 165 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/12/2017 10:30 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Revd. from: MARK LEIKER

Company: BEREXCO LLC

Phone: (316) 265-3311

Proposed
Plugging
Method:

PUMP BOTTOM WITH 50 SX CMT & 150# HULLS, SPACER TO 1750' & CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 12/12/2017 12:30 PM

KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP BOTTOM WITH 50 SX CMT & 150# HULLS. SPACER TO 1750'. PUMPED 150 SX CMT TO SURFACE. PRESSURED TO 1400#. TOPPED OFF WITH 25 SX CMT. FILLED ANNULUS WITH 10 SX CMT. PRESSURED TO 210#.

Perfs:

Top	Bot	Thru	Comments
4710	4714		

INVOICED
JAN 13 2018

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: CSG

District: 01

Signed Larry Harris
(TECHNICIAN)

12/21/17
RECEIVED
DEC 21 2017
KCC DODGE CITY

5A