

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-22178-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 12-30S-12E  
3861 feet from S Section Line, 1745 feet from E Section Line  
Lease Name: CODY Well #: 4  
County: ELK Total Vertical Depth: 1558 feet

Operator License No.: 7786  
Op Name: CODY, KEN L.  
Address: 1125 RD 27  
LONGTON, KS 67352

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1308		
PROD	4.5	1556		167 SX
SURF	8.625	40		15 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: KEN CODY Company: \_\_\_\_\_ Phone: (620) 642-6123

Proposed Plugging Method: Gel hole. Spot cement plug at 1308-1258. Spot 50 ft cement plug 800-750. Cement from 350 ft to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 12/12/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Bridge plug set at 1309 ft. Ran 1" tubing to 1206' gelled hole spotted 5 sacks cement. Pulled up to 700' and spotted 5 sacks plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 40 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1546	1547		
1223	1227		

RECEIVED  
KCC DIST # 3  
DEC 26 2017  
CHANUTE, KS

DS  
INVOICED


JAN 16 2018

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)