


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 7 Twp. 20S Rge. 20W-E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines E/2 SE SW
Lease Owner American Energies Corporation
Lease Name Smith "A" Well No. 4
Office Address 680 Fourth Financial Ctr., Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole
Date Well completed April 17, 1980
Application for plugging filed Verbal Application 1980
Application for plugging approved Verbal Approval 1980
Plugging commenced April 17, 1980
Plugging completed April 17, 1980
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,420'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	214'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,420 ft. (rotary total depth) to 650 ft. Set plug at 650 ft. and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 650 ft. to 180 ft. Set plug at 180 ft. and cemented with 30 sacks cement. Filled hole with heavy rotary mud from 180 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1980
3-30-89


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick
Dean Britting, Agent (Agent of owner ~~XXXXXXXXXXXXXXXXXXXX~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 28th day of April, 1980

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY American Energies Corporation
 FARM Smith "A" NO. 4

SEC. 7 T. 20S R. 20W
 LOC. E/2 SE SW
 COUNTY Pawnee

ROTARY TOTAL DEPTH 4,420'
 COMM. April 9, 1980 COMP. April 17, 1980
 CONTRACTOR H-30, INC. (Rig #2)
 ISSUED April 28, 1980

CASING

10 3/4"
 8 5/8" Set at 214' cemented w/160 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 2,244' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	215'
Sand and Shale	360'
Shale and Sand	1,360'
Shale	2,325'
Shale and Lime	2,840'
Shale	3,050'
Shale and Lime	3,495'
Lime and Shale	3,915'
Lime	4,420'
Rotary Total Depth	4,420'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas)
 County of Sedgwick) SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 28th day of April, 1980.

Elsie Willison
 Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED
 STATE CORPORATIONS COMMISSION
 APR 30 1980
 (CORPORATION DIVISION)
 Wichita, Kansas