


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 20 Twp. 20S Rge. 19 (W)  
Location as "NE/CNW/SW" or footage from lines Approx. Gen. NE SW  
Lease Owner Jay Bee Oil Company, Inc.  
Lease Name Bartonek Well No. 1  
Office Address 511 Union Center Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 31 1967  
Application for plugging filed Verbal Approval 19    
Application for plugging approved Verbal Approval 19    
Plugging commenced May 31 1967  
Plugging completed May 31 1967  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	406'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,260' feet (rotary total depth) to 600 feet. Set bottom plug at 600 feet and cemented with 25 sacks of cement. Filled hole with heavy rotary mud to 380 feet. Set plug at 380 feet and cemented with 20 sacks of cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 8 sacks of cement. 2 sacks cement in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1967

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor H-30, Inc. (If additional description is necessary, use BACK of this sheet)  
Address 200 North Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B Romer  
200 North Main St., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1967

Martha Hartpence  
Martha Hartpence Notary Public.

My commission expires April 21, 1971

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

15.145.20011.0000


COMPANY Jay Bee Oil Company, Inc.  
 FARM Bartonek NO. 1

SEC. 20 T. 20S R. 19W  
 LOC. approx. Cen NE SW

TOTAL DEPTH 4260'  
 COMM. May 17, 1967  
 SHOT OR TREATED  
 CONTRACTOR H-30, Inc.  
 ISSUED

COMP. May 31, 1967

COUNTY Pawnee



CASING

20	10		
15	8-5/8"	406'	cemented with 250 sacks ELEVATION 2187 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Rock & Clay	72			
Sand	85			
Shale	409	Anhydrite	1329	+ 858
Shale & Clay	525	Base Anhydrite	1358	+ 829
Shale	767	Heebner	3644	-1457
Sand & Red Bed	952	Toronto	3662	-1475
Shale & Red Bed	1331	Lansing	3692	-1505
Anhydrite	1355	Base K. C.	4033	-1846
Shale & Lime	1415	Pawnee	4101	-1914
Shale & Shells	1975	Cherokee Shale	4182	-1995
Shale	2100	Cherokee Sand	4183	-1996
Lime & Shale	2230	Mississippi	4244	-2057
Lime	2558	Log T. D.	4258	-2071
Lime & Shale	3690	Rotary T.D.	4260	-2073
Lime	3825			
Lime & Shale	3925			
Lime	3988			
Lime & Shale	4188			
Shale	4217			
Lime & Shale	4260			
Rotary Total Depth	4260			

ELECTRIC LOG TOPS:

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUN 5 1967

CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer  
 Arlo B. Romer

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss

SUBSCRIBED AND SWORN to before me a Notary Public in and for said county and state, this 1st day of June, 1967.

Martha Hartpence  
 Martha Hartpence Notary Public

My Commission Expires: April 21, 1971