


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above Section Plat

Pawnee County, Sec. 24 Twp. 20S Rge. 19W (E) (W)
Location as "NE/CNW/SW/X" or footage from lines SE NW NE
Lease Owner National Cooperative Refinery Association
Lease Name Starmer Well No. No. 1
Office Address 404 Lincoln Tower Building, Denver, Colorado 80203
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed August 14 1973
Application for plugging filed August 14 1973
Application for plugging approved August 14 1973
Plugging commenced August 14 1973
Plugging completed August 14 1973
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4130 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 434' | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug to 500', cmt. w/50 sx 50-50 pozmix,
Plug @ 240' w/25 sx 50-50 pozmix,
Build Bridge @ 40' to hold kelly up and
put 10 sx cmt.
2 sx in rathole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1973


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

Sworn to before me this 17th day of August, 1973



Linda C. Mowrey
Notary Public.

DRILLERS LOG

No. 1 Starmer

CASING RECORD:

8-5/8" @ 434'
w/250 SX cement

COMPANY: Nat'l Coop. Refinery Assn.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: August 2, 1973

COMPLETED: August 14, 1973

DESCRIPTION:

SE NW NE
24-205-19W
Pawnee County,
Kansas

TOTAL DEPTH: 4130'

ELEVATION:

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|------------------|-------------|-----------|---|
| Surface Hole | 0 | 210 | RECEIVED STATE CORPORATION COMMISSION SEP 17 1973 CONSERVATION DIVISION (Wichita, Kansas) |
| Sand | 210 | 275 | |
| Shale | 275 | 435 | |
| Shale & Redbed | 435 | 705 | |
| Sand | 705 | 840 | |
| Shale & Redbed | 840 | 1267 | |
| Anhydrita | 1267 | 1294 | |
| Shale & Shells | 1294 | 2215 | |
| Lime & Shale | 2215 | 3595 | |
| Lime | 3595 | 4030 | |
| Lime & Sand | 4030 | 4037 | |
| Lime | 4037 | 4130 | |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 17th day of August, 1973.

Linda C. Mowrey
Notary Public

My Commission Expires:

May 24, 1977

