

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 9 TWP. 20S RGE. 22E 19
Location as in quarters or footage from lines:

NE SE SE

Lease Owner National Cooperative Refinery Association

Lease Name Matoush #3 Well No. _____

Office Address Box 6 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 2-10-82

Plugging completed 2-26-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4225'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	135'	none
				5-1/2"	4225'	3036'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 4125' and ran 5 sacks cement. Shot casing @3545', 3220' and 3025'. Pulled a total of 94 joints of pipe. Plugged well with 4 sacks hulls, 15 sacks gel, 75 sacks cement, 1 sack hulls, 10 sacks gel, released plug and displaced with 75 sacks 50/50 pos, 4% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

MAR 4 1982

(Signature) R. Darrell Kelso

CONSERVATION DIVISION
Wichita, Kansas

Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd. day of March, 19 82



Irene Hoover
Notary Public.

My Commission expires: _____

COMPANY M. B. Armer

SEC. 9 T. 20 R. 19W

FARM Matoush

LOC. NE SE SE

NO. 3 FILE

TOTAL DEPTH 4225'

COUNTY Pawnee

COMM. 6/27/55


COMP. 7/10/55

KANSAS

SHOT OR TREATED

CONTRACTOR Armer, Inc.

ISSUED



CASING

20	10	
15	8	135'
12	6	
13	5	4225'

ELEVATION 2244 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale & Shells	135
Shale, Shells & Red Bed	710
Shale & Red Bed	795
Sand	1010
Shale, Shells & Red Bed	1365
Shale & Red Bed	1380
Anhydrite	1410
Shale & Lime	1585
Shale & Shells	1955
Shale & Lime	2800
Broken Lime	2910
Shale & Lime	3025
Shale	3185
Shale & Lime	3475
Lime	3535
Shale & Lime	3735
Lime	3835
Lime & Shale	3875
Lime	4190
Sand & Lime	4225

FORMATION TOPS

HREBNER	3660
TORONTO	3677
LANSING	3704
CONGLOMERATE SAND	4168

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By *C. P. Spangenberg*

STATE OF KANSAS
 COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 13th day of July, 1955.

RECEIVED
 Notary Public CORPORATION COMMISSIONER

JAN 21 1962
 CONSERVATION DIVISION
 Wichita, Kansas