


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Flat

Pawnee County. Sec. 9 Twp. 20 Rge. 15 (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NE 1/4  
Lease Owner M. B. Armer  
Lease Name Ellis "B" Well No. 1  
Office Address 711 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed Sept. 30 19 59  
Application for plugging filed Sept. 30 19 59  
Application for plugging approved Sept. 30 19 59  
Plugging commenced Sept. 30 19 59  
Plugging completed Sept. 30 19 59  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4230 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	137	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy Rotary mud to 135 Ft., set plug and cement with 20 sacks cement and 1/2 sack hulls through Drill Pipe. Mud hole to 35 feet, set plug and cement with 10 sacks cement and 1/3 sack hulls to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Armer Inc.  
Address 709 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 7 day of October, 19 59

Adela Petrik  
Notary Public.

My commission expires November 5, 1962



RECEIVED  
STATE CORPORATION COMMISSION

OCT 8 1959

10-8-59

CONSERVATION DIVISION

15.145.01045.0000

**KANSAS GEOLOGICAL SOCIETY**  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **M. B. Armer**  
 FARM **Ellis "B"** NO. **1**

SEC. **9** T. **20** R. **19W**  
 LOC. **SE SW NE 1/4**

TOTAL DEPTH **4230'**  
 COMM. **9/19/59** COMP. **10/1/59**  
 SHOT OR TREATED  
 CONTRACTOR **Armer, Inc.**  
 ISSUED

COUNTY **Pawnee**

KANSAS



CASING  
 20 10  
 15 8 **137'**  
 12 6  
 13 5

ELEVATION **2257K.B.**  
**2254D.F.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	190'
Shale, Red Bed & Sand	1420
Red Bed & Shale	1430
Anhydrite	1460
Shale & Shells	2085
Lime	2140
Lime & Shale	3360
Shale & Shells	3435
Shale & Lime	3830
Lime	4000
Lime & Shale	4050
Lime	4140
Lime & Shale	4195
Shale & Sand	4216
Conglomerate	4230

2757  
 1430  
 ---  
 1327

Formation Tops:

Heebner	3707'	-1450
Toronto	3727'	-1470
Lansing	3755'	-1498
Base K. C.	4068'	-1811
Conglomerate	4210'	-1953
T. D.	4230'	-1973

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By *L. C. Sponenberg*  
 L. C. Sponenberg

STATE OF KANSAS )  
 )  
 COUNTY OF SEDGWICK ) ss.

Subscribed and sworn to me, a Notary Public, in and for said County and State, this 7th day of October, 1959

*Adela Petrik*  
 Notary Public

My Commission Expires November 5, 1962

RECEIVED  
 STATE CORPORATIONS COMMISSION

OCT 8 1959

CONSERVATION DIVISION  
 Wichita, Kansas